BRUHATH BANGALURU MAHANAGARA PALIKE
YELAHANKA ZONE

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule B"

Name of the work : Annual Maintenance and repairs to electrical installation at J C yelahanka Zonal office Building in Byatrayanapura in ward no 7

Sl.No	Qty	Description Of Work	Unit	Quoted Rates	
				In figures	In words
1	1	Licenced electrician wiremen fitter with tools (Skilled) Rs.13365/Person/Month. Rs.13365*12=1,60,380/Person/Year. KAE71LWA 2015 Dated 04-08-2016	Per Person	145380.00	Rupees One Lakh(s) Forty Five Thousand Three Hundred Eighty Only
2	1	a).Helper (Electrical) (Semi-Skilled) Rs.11011/Person/Month. Rs.11011*12=132132/Person/Year. KAE71LWA 2015 Dated 04-08-2016	Per Person	118132.00	Rupees One Lakh(s) Eighteen Thousand One Hundred Thirty Two Only
3	1	Annual Maintenance of 180 KVA D.G. Set Existing A.M.C. including of labour charges only for replacing the spare parts and periodically checkup of D.G. AMF panel (Without operator)	Each	30000.00	Rupees Thirty Thousand Only
4	1	Supplying & Changing of Alternator AVR.(Automatic Voltage Regulator)	Nos	1000.00	Rupees One Thousand Only
5	1	Supplying & Changing of Dynamo repair Kit such as Corbons, Bearings & Diode Etc,.	Nos	200.00	Rupees Two Hundred Only
6	6	Supplying and fixing HRC fuse link on existing switch fuse base with watt loss as per IS-13703. 3) 125Amps	Each	100.00	Rupees One Hundred Only
7.0	3	Supplying wall mounting fan suitable to operate at single-phase 230v A.C. supply.400mm Sweep	Each	1000.00	Rupees One Thousand Only
8	19	Supply of 230 V CFL Lamp Holder 2 pin	No	20.00	Rupees Twenty Only
9	50	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper conductor single core wire in open or concealed system of wiring as per IS-694:1990 & confirming to GTP of GROUP -A.1.5 sqmm	Rmt	5.00	Rupees Five Only
	50	4)4 sqmm	P/Mtr	6.00	Rupees Six Only
10	60	Supplying and fixing/replacing of 6/16/32Amps electrical accessories on existing switch board. GROUP A 6Amps SP Switch		5.00	Rupees Five Only
11	25	6Amps 3 way 5 pin Socket	Nos	5.00	Rupees Five Only
12	15	16 Amps SP switch	No	20.00	Rupees Twenty Only
13	15	16 Amps 3 way 5 pin socket	No	20.00	Rupees Twenty Only
14	10	32 Amps Bakelite DP	No	20.00	Rupees Twenty Only
15	10	16/6 Amps combined plug and socket wit control switch	No	20.00	Rupees Twenty Only

16	60	2'/4' - 36/40 Watts Fluorescent Tubes: Supplying and fixing of 36W Fluorescent Tube with 36W power consumption with initial lumen of 2750 (3000 deg K / 4000 deg K) with rated avg life of greater than 10000 hrs.	No	20.00	Rupees Twenty Only
17	20	Supplying and fixing of 20/40 Watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes : Supplying and fixing of 20/40 Watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes, Class H Insulated copper wire, Vacuum impregnated high quality with Low loss silicon steel lamination operated on 240V,50Hz supply with IEC 60920 (Safety) & IEC 60921(Performance)	No	100.00	Rupees One Hundred Only
18	35	Supplying of of 2 pin/4 pin 18W CFL Lamp	No	80.00	Rupees Eighty Only
19	15	Condenser for ceiling fan/MV/SV/MH and other luminaires Upto 4 mfd	No	30.00	Rupees Thirty Only
20	10	Upto 8 mfd	No	30.00	Rupees Thirty Only
21	10	Stepped Fan Regulator.	Each	100.00	Rupees One Hundred Only
22	3	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 220v A.C.50 Hz 12/24v D.C.	Each	100.00	Rupees One Hundred Only
23	6	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes 11) 95 sq mm long barrel	Each	100.00	Rupees One Hundred Only
	3	15) 240 sq mm long barrel	Each	250.00	Rupees Two Hundred Fifty Only
24	1	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and Complete wiring as required confirming IEC 60898. 6) 05-32 Amps TPN	Each	300.00	Rupees Three Hundred Only
25	1	Fixing of ..... Amps TPST / change over switch / Contactor along with neutral link with screws, bolts, nuts and wiring using required capacity wires and circuit labeling.00A to 250A TPST	Each	100.00	Rupees One Hundred Only
26	3	Rewinding a ... mm ceiling fan/after using necessary gauge annealed and insulated copper wire with necessary insulating, separators vibration arresting shellac, etc including replacement of bearings if any transportation to and from the spot to workshop inclusive of releasing the refixing.1200MM	Each	150.00	Rupees One Hundred Fifty Only

I am prepared to take up the above work at rates quoted in the Schedule 'B'

Contractor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone